

**City of Anchorage**

1306 Evergreen Road  
Anchorage, KY 40223

Gary Burkhead Director of Public Works  
Mobile: 502.299.5598

**Due Date: 7 May 2021**

**2021 Capital Roads Improvement Project  
Bid Description of Asphalt Work**

**Phase #1**

**Roads to be Paved (marked with road paint):**

1. Bellewood Road "T" intersection (Bellewood Road at Owl Creek Lane): mill six inches deep with compacted gravel and overlay with asphalt.
2. Cave Spring Place Road North (north of Lucas Lane including the complete cul-de-sac).
3. Anchor Way (Lucas Lane to Crest Arm Road).
4. Captain's Bridge and Anchor Way (Little Hill Ln to Lucas Ln)
5. Lucas Lane (12409 Lucas Lane to 12203 Lucas Lane)
  - a. (note: replace 15 x 19 x 3.5 ft. Speed hump)
6. Osage Road East three sections as follows: Stonegate Road heading east to speed hump; speed hump to new asphalt in front of 12004 East Osage Road; new asphalt to Forest School Lane. (Speed hump does not get replaced).
7. Old Bridge Place apron entrance.
8. Anchorage City Hall driveway circle (1306 Evergreen Road) from right side parking to opposite side of circle (where asphalt edge is broken) mill with 3 inches of compacted gravel on inside turns.
9. Linden Drive (Arbor Drive East to dead end).
  - a. (note: replace 15 x 19 x 3.5 ft. Speed hump)

**Speed Humps to be replaced: (8)**

1. 1104 Old Harrods Creek 15 x 19 x 3.5 ft.
2. 11101 Beech Road 15 x 19 x 3.5 ft.
3. 902 Bellewood Road/north of Beech Road 15 x 21 x 3.5 ft.
4. 1705 Evergreen road 15 x 21 x 3.5 ft.
5. 12409 Lucas Lane 15 x 19 x 3.5 ft.
6. 705 Linden Dr 15 x 19 x 3.5 ft. (straighten)
7. 1908 Evergreen Rd 15 x 19.6 x 3.5 ft.
8. 12207 Log Cabin Lane (extension of Surrey Lane) 15 x 14 x 3.5 ft

**Add (1) New Speed Hump:**

1. 805 Surrey Lane. 15 x 13 x 3.5 ft

**Remove (1) Speed Hump:**

1. On Evergreen Road by 11704 Owl Creek Lane

**Walking Path Sections to Replace (3) (marked with paint):**

1. 903 Bellewood Road
2. 1705 Evergreen road
3. 1103 Old Harrods Creek Road

**Phase #2** Bid: work to be completed upon completion of sewer work. Estimated within next twelve months.

**Roads to be Paved:**

1. Log Cabin (Evergreen Road to Glenbrook Road)
10. Replace speed hump
  
2. Glenbrook Road (Woodland Road Island to Ridge Road)
11. Remove speed hump close to Ridge Road
12. Remove speed hump at 1100 Glenbrook Road
13. Install a new speed hump by 1107 Glenbrook Road by telephone pole. 15 x 18 x 3.5 ft.

# Paving Specification

## **Clean, tack and Pave with 1 ½" Compacted asphalt surface**

Re: Paving Marked City Streets

Note: Roadways are marked with paint to indicate the start and finish of roads to be paved. Not all roads are a total paving. All Stripes removed on roadways need be repainted. (To include: Thermo Stop Bars, RXR and Pave Striping-Permanent-4IN.)

### **Scope of Work**

Cut edge keys.

Mill and broom clean existing pavement to a depth of 1 ½".

Haul millings off site.

Prime with tack.

Pave with 1 ½ compacted asphalt surface.

Stripe where previous stripe exists.

Provide Traffic Control if needed.