

Surrey Lane Paving Specification

Clean, tack and Pave with 2" of compacted base asphalt and 1" of surface asphalt.

Re: Paving Marked City Street

Note: Roadway is marked with paint to indicate the start and finish of road to be paved. Pavement should match up to driveways. City of Anchorage does not want winter mix used in paving. No trees will be removed.

Scope of Work: Asphalt Pavement and Drainage Improvement

Remove 2 sections of metal drainage tile.

Supply and install 2 new sections totaling approximately 50'.

Pipe to be 12" C-900 heavy wall pipe.

Head wall to be installed on south side of pipe located in the 90-degree turn.

Clean the silt out of the immediate ditch, 10' +/-.

Raise Water main sleeve to level of roadway.

Grade existing stone base.

Compact, shape and roll.

Haul off any excess materials.

Cut edge keys.

Pave with 2" of compacted base asphalt.

Pave with 1" of surface asphalt.